

AD-A106 644

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. NORTH TWIN LAKES DAM (MO 31216), M--ETC(U)

OCT 80 R S DECKER, G B JAMISON, G ULMER


DACW43-81-C-0003

NL

UNCLASSIFIED

1 of 2

3/10/81



AD A106644

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A106	644
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program North Twin Lakes Dam (MO 31216) Cape Girardeau, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Hoskins-Western-Sonderregger, Inc.		6. CONTRACT OR GRANT NUMBER(s) 15 DACW43-81-C-0003
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSD-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSD-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		12. REPORT DATE 11 October 1980
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 12 17 1		13. NUMBER OF PAGES Approximately 70
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION STATEMENT (of this Report) Approved for release; distribution unlimited	10	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) 6	Rey S. /Decker Gordon /Jamison Garold /Ulmer Harold P. /Hoskins	
18. SUPPLEMENTARY NOTES	National Dam Safety Program. North Twin Lakes Dam (MO 31216), Mississippi - Kaskaskia - St. Louis Basin, Cape Girardeau County, Missouri. Phase I Inspection Report.	
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 75 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

394131

INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

RESPONSIBILITY. The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

CLASSIFICATION. Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

COMPLETION GUIDE

General. Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

Block 1. Report Number. Enter the unique alphanumeric report number shown on the cover.

Block 2. Government Accession No. Leave blank. This space is for use by the Defense Documentation Center.

Block 3. Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

Block 4. Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

Block 5. Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

Block 6. Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

Block 7. Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

Block 8. Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

Block 9. Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

Block 10. Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

Block 11. Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

Block 12. Report Date. Enter here the day, month, and year or month and year as shown on the cover.

Block 13. Number of Pages. Enter the total number of pages.

Block 14. Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

Blocks 15 & 15a. Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

Block 16. Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 17. Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

Block 18. Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with ... Translation of (or by) ... Presented at conference of ... To be published in ...

Block 19. Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

Block 20. Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

NORTH TWIN LAKES DAM
CAPE GIRARDEAU COUNTY, MISSOURI
MISSOURI IDENTIFICATION NO. MO 31216

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY
HOSKINS-WESTERN-SONDEREGGER, INC.
CONSULTING ENGINEERS
LINCOLN, NEBRASKA

UNDER DIRECTION OF
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
FOR
GOVERNOR OF MISSOURI

OCTOBER, 1980

Accession For	
NTIC GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
and/or	
Dist	al
A	

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

DTIC
ELECT
S OCT 30 1981 D
D



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 TUCKER BOULEVARD, NORTH
ST. LOUIS, MISSOURI 63101

SUBJECT: North Twin Lakes Dam - MO 31216

This report presents the results of field inspection and evaluation of the North Twin Lakes Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY:

SIGNED

Chief, Engineering Division

7 MAY 1981

Date

APPROVED BY:

SIGNED

Colonel, CE, District Engineer

11 MAY 1981

Date

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
	SECTION 1 - PROJECT INFORMATION	
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	3
	SECTION 2 - ENGINEERING DATA	
2.1	Design	7
2.2	Construction	7
2.3	Operation	7
2.4	Evaluation	7
	SECTION 3 - VISUAL INSPECTION	
3.1	Findings	8
3.2	Evaluation	10
	SECTION 4 - OPERATIONAL PROCEDURES	
4.1	Procedures	11
4.2	Maintenance of Dam	11
4.3	Maintenance of Operating Facilities	11
4.4	Description of Any Warning System in Effect	11
4.5	Evaluation	11
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	12
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	14
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	15
7.2	Remedial Measures	15

APPENDIX A - MAPS

Plate A-1
Plate A-2
Plate A-3

Vicinity Topography
Location Map
Seismic Zone Map

APPENDIX B - PHOTOGRAPHS

Plate B-1		Photo Index
Plate B-2	Photo No. 2	Overview from Right Upstream Bank
	Photo No. 3	Downstream Slope from Left End
Plate B-3	Photo No. 4	Crest of Dam from Left End
	Photo No. 5	Upstream Slope from Left End
Plate B-4	Photo No. 6	Crawdadd or Salamander Holes on Upstream Slope
	Photo No. 7	Closeup View of Mud Mounded at the Top of Dauber Holes near Water's Edge
Plate B-5	Photo No. 8	Inlet to Principal Spillway (18-inch CMP)
	Photo No. 9	Looking Upstream from Station 2+00
Plate B-6	Photo No. 10	Looking Along Downstream Crest at Outlet of Pipe Spillway
	Photo No. 11	Iron Stained Seepage Coming Out of the Left Abutment Trough at Elevation of the Outlet of the Pipe Spillway
Plate B-7	Photo No. 12	Outlet of the Principal Spillway Pipe
	Photo No. 13	Outlet of Principal Spillway Pipe and Plunge Pool
Plate B-8	Photo No. 14	Rodent Hole on Downstream Slope about Four to Five Feet Above Toe
	Photo No. 15	View Looking Across the Emergency Spillway from Right End of Dam (Looking North)
Plate B-9	Photo No. 16	View Looking Upstream Through the Spillway
	Photo No. 17	View Looking Downstream Through the Spillway
Plate B-10	Photo No. 18	View Looking Right to Left (North to South) Across the Reservoir
	Photo No. 19	Downstream Hazards Just Below Dam
Plate B-11	Photo No. 20	Downstream Hazards Just Below Dam
	Photo No. 21	Houses Downstream from Dam on Right Side
Plate B-12	Photo No. 22	Houses Downstream from Dam on Right Side
	Photo No. 23	View of Downstream Hazards
Plate B-13	Photo No. 24	View of Downstream Hazards

APPENDIX C - PROJECT PLATES

Plate C-1

Phase I - Plan and Centerline Profile
of Dam

Plate C-2

Phase I - Maximum Cross Section of Dam
at Sta. 1+50 and Profile
along Centerline of Emergency
Spillway

APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 and D-2

Hydrologic Computations

Plate D-3

Principal Spillway Discharge Rating
Curve

Plate D-4

Emergency Spillway Discharge Rating
Curve

Plate D-5

Elevation-Area Curve

Plates D-6 through D-53

Computer Input and Output for Ratios
of PMF

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM
ASSESSMENT SUMMARY

Name of Dam	North Twin Lakes Dam
State Located	Missouri
County Located	Cape Girardeau County
Stream	Tributary to Tributary to Ramsey Branch
Date of Inspection	October 30, 1980

North Twin Lakes Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderegger, Inc. The purpose of the inspection was to make an assessment of the general conditions of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers.

North Twin Lakes Dam has a height of twenty-seven (27) feet and a storage capacity at the minimum top elevation of the dam of eighty-seven (87) acre-feet. In accordance with the guidelines, a small size dam has a height greater than or equal to twenty-five (25) feet but less than forty (40) feet and a storage capacity greater than or equal to fifty (50) acre-feet but less than one thousand (1,000) acre-feet. The size classification is determined by either the storage capacity or height, whichever gives the larger size category. North Twin Lakes Dam is classified as a small size dam.

In accordance with the guidelines and based on visual observation, the dam is classified as having a high hazard potential. Failure would threaten life and property. The estimated damage zone extends approximately one (1) mile downstream of the dam. Within the damage zone are eight dwellings and two garages (0.05 to 0.2 miles downstream) and one dwelling (0.35 miles downstream).

Our inspection and evaluation indicates that the spillways meet the criteria set forth in the recommended guidelines for a small dam having a high hazard potential. Considering the small volume of water impounded and the broad downstream floodplain, one-half of the Probable Maximum Flood is the appropriate spillway design flood. The spillways will pass the 100-year flood (1% probability flood - a flood having a one percent chance of being exceeded in any one year) without overtopping the dam. The spillways will pass 50% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

North Twin Lakes Dam is in excellent condition. The deficiencies noted are the growth of trees on the downstream slope, rodent activity on the downstream slope and the lack of seepage and stability analyses as required by the guidelines for all dams having a high hazard potential.

Design data were not available for this dam. Based on visual observation and on the analyses made during and subsequent to the inspection, the following recommendations are made:

a. Alternatives.

- (1) The spillways will accommodate 50 percent of the probable maximum flood without overtopping the dam. No alternatives are required.

b. Operation and Maintenance Procedures.

- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by an engineer experienced in the design and construction of dams.
- (2) The trees growing on the downstream crestline and slope should be removed. Tree removal should be done under the guidance of an engineer experienced in the design and construction of dams.
- (3) Rodent holes on the downstream slope should be repaired. A program should be developed to eliminate rodent activity on the dam.
- (4) The crawfish holes along and above the water's edge are shallow and probably do not endanger the dam. They do, however, constitute a weakness where erosion can begin. In lieu of attempting to eliminate the crawfish population, it is recommended that monitoring of the holes and repair of eroded areas become a part of the maintenance program.
- (5) The low volume seep in the left (south) abutment trough should be monitored on a periodic basis.
- (6) The excellent maintenance program that accounts for the neat and clean appearance of this dam should be continued.
- (7) A program of periodic inspections should be initiated. Records of the inspections should be made a part of this project file.

Rey S. Decker

Rey S. Decker
E-3703

Gordon J. Jamison

Gordon Jamison

Garold Ulmer

Garold Ulmer
E-19246

H. P. Hoskins

Harold P. Hoskins, Chairman of the Board
Hoskins-Western-Sonderegger, Inc.
E-8696




PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
NORTH TWIN LAKES DAM - MO 31216
CAPE GIRARDEAU COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of North Twin Lakes Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams", dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances.

- (1) Embankment. The embankment is an earthfill structure approximately 300 feet in length and 27 feet in height with a maximum storage capacity at the minimum top of dam elevation of 87 acre-feet. Photo No. 1 and Plate A-1 show a small dam and reservoir approximately 900 feet upstream from this dam. Survey data were obtained on the upstream dam and its spillways during the inspection. This information was used in the hydraulic/hydrologic analyses presented in Section 5 of this report.
- (2) Principal Spillway.
 - (a) Inlet Structure. The inlet structure is an 18-inch corrugated metal pipe riser. The crest of the riser is at elevation 444.8 feet and the bottom is at elevation 427.2 feet. There is a trash rack and straining screen over the inlet. Photo No. 8 shows the inlet to the riser.

- (b) Conduit. The conduit consists of 121 feet of 15-inch corrugated metal pipe. It has an invert elevation at the floor of the riser of 427.2 feet and an outlet invert elevation of 422.5 feet. The inlet is at Station 1+50 and the outlet is downstream from Station 1+30. Photos 12 and 13 show the outlet end of the conduit.
- (c) Stilling Basin. There is no constructed stilling basin. The principal spillway outlets into the natural channel where a plunge pool has developed by scouring down to bedrock. Photo No. 13 shows the plunge pool.
- (3) Emergency Spillway. The emergency spillway is uncontrolled and is located in the right (north) abutment of the dam. It consists of a vegetated earth entrance channel leading to a parabolic shaped depression in the asphalt surfaced road that crosses the dam. The road section serves as the control section. Flows downstream from the control section will follow an asphalt surfaced street through a residential area downstream from the dam. Photos 15, 16 and 17 show views of the emergency spillway.
- (4) Low-Level Outlet. There is no low-level outlet.
- (5) Pertinent physical data are given in paragraph 1.3.
- b. Location. The dam is located in the east-central portion of Cape Girardeau County, Missouri, approximately 2 miles west of the northwest corner of the City of Cape Girardeau, as shown on Plate A-2. The dam and reservoir are shown on Plate A-1 in the NW 1/4 Sec. 34, T.31N., R.13E.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. North Twin Lakes Dam has a height of 27 feet and a storage capacity of 87 acre-feet. This dam is classified as a small size dam. A small size dam has a height greater than or equal to 25 feet but less than 40 feet and a storage capacity greater than or equal to 50 acre-feet but less than 1,000 acre-feet. The size classification is determined by either the storage or height, whichever gives the larger size category.
- d. Hazard Classification. Guidelines for determining hazard classification of dams and impoundments are presented in the guidelines as referenced in paragraph 1.1c above.

Aerial photographs of the downstream damage zone of this dam were taken in October, 1980. These photographs were used as reference in the field observations of the damage zone which were made during the inspection. Based on the field observations and on the referenced guidelines, this dam is in the High Hazard Potential

Classification. The estimated damage zone extends approximately one mile downstream of the dam. Within the damage zone are eight dwellings and two garages (0.05 to 0.2 miles downstream) and one dwelling (0.35 miles downstream).

- e. Ownership. This dam is owned by the Twin Lakes Home Owners Association, Route 2, Box 533B, Cape Girardeau, Missouri 63701 - Attention: John Mills, President.
- f. Purpose of Dam. The dam was built to provide a recreational reservoir for the home owners.
- g. Design and Construction History. Information provided by Mr. C. R. Hertling, local home owner, and Mr. John Mills indicates that the dam was built about 10 years ago by a Calvin Phillips under the supervision of the Soil Conservation Service, Jackson, Missouri. They said the dam had a core trench about 12 feet wide at the bottom and 20 feet across the top. No other information was available.
- h. Normal Operating Procedure. There are no operating facilities for this dam. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillways.

1.3 PERTINENT DATA

- a. Drainage Area. 70.1 acres (0.11 square miles).
- b. Discharge at Damsite.
 - (1) All discharges at the damsite are through the following:
 - (a) An uncontrolled principal spillway consisting of an 18-inch corrugated metal pipe drop inlet which is connected to a 15-inch corrugated metal pipe conduit that extends through the base of the dam.
 - (b) An uncontrolled emergency spillway formed by a parabolic shaped depression in the road profile at the right (north) end of the dam.
 - (2) Estimated maximum flood at damsite - Mr. Hertling and Mr. Mills indicated that the emergency spillway had flowed 6 to 8 inches deep about five years ago following a 7 to 8-inch rainstorm.
 - (3) The principal spillway capacity varies from 0 c.f.s. at elevation 444.8 feet to 13 c.f.s. at the crest of the emergency spillway (elevation 447.3 feet) to 14 c.f.s. at the minimum top of dam (elevation 449.2 feet).

(4) The emergency spillway capacity varies from 0 c.f.s. at its crest (elevation 447.3 feet) to 511 c.f.s. at the minimum top of dam (elevation 449.2 feet).

(5) Total spillway capacity at the minimum top of dam is 525 c.f.s. \pm .

c. Elevations (feet above M.S.L.)

(1) Observed pool - 443.0

(2) Normal pool - 444.8

(3) Spillway crests

Principal - 444.8

Emergency - 447.3

(4) Maximum experienced pool - 447.9 \pm

(5) Top of dam (minimum) - 449.2

(6) Streambed - 422 \pm

(7) Maximum tailwater - unknown

d. Reservoir. Length (feet) of pool.

(1) At principal spillway crest - 850 \pm)

(2) At emergency spillway crest - 850 \pm) } At base of upper dam

(3) At top of dam (minimum) - 900 \pm) }

e. Storage (acre-feet).

(1) Observed pool - 47 \pm

(2) Normal pool - 57 \pm

(3) Spillway crests

Principal - 57 \pm

Emergency - 76 \pm

(4) Maximum experienced pool - 79 \pm

(5) Top of dam (minimum) - 87 \pm

f. Reservoir Surface (acres).

(1) Observed pool - 5.5 \pm

- (2) Normal pool - 6.0±
- (3) Spillway crests
 - Principal - 6.0±
 - Emergency - 6.6±
- (4) Maximum experienced pool - 6.7±
- (5) Top of dam (minimum) - 7.1±

g. Dam.

- (1) Type - Earthfill
- (2) Length - 300 feet
- (3) Height - 27 feet
- (4) Top width - 25 feet
- (5) Side slopes
 - (a) Downstream - 1V on 3.0± H
 - (b) Upstream - 1V on 3.5± H
- (6) Zoning - unknown
- (7) Impervious core - Mr. Hertling stated it had a core trench with about 12-foot bottom width and 20-foot top width
- (8) Cutoff - unknown
- (9) Grout curtain - none
- (10) Wave protection - vegetated earth
- (11) Drains - unknown

h. Diversion Channel and Regulating Tunnel. None

i. Spillways.

(1) Principal

- (a) Type - uncontrolled, 18-inch diameter corrugated metal pipe drop inlet connected to a 15-inch corrugated metal pipe conduit that extends through the base of dam

- (b) Crest (invert) elevation - 444.8 feet

Outlet - 422.5 feet

(c) Length - 121 feet

(2) Emergency

(a) Type - Depression in road profile at right abutment

(b) Control section - Paved (asphalt mat) road surface about 21 feet wide

(c) Crest elevation - Minimum top of road - 447.3 feet

(d) Upstream channel - Well vegetated, open

(e) Downstream channel - Asphalt surfaced road and side ditches (see Photos 16 and 17)

j. Regulating Outlets. None

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

No design data were available for this dam.

2.2 CONSTRUCTION

No construction data were available. It was reported by Mr. Hertling and Mr. Mills that the dam was constructed approximately 10 years ago by a Mr. Calvin Phillips, and that construction was supervised by the Soil Conservation Service, Jackson, Missouri.

2.3 OPERATION

There are no operation facilities for this dam.

2.4 EVALUATION

- a. Availability. No data were available.
- b. Adequacy. The field surveys and visual observations presented in this report are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. Not applicable.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

- a. General. A visual inspection of the North Twin Lakes Dam was made on October 30, 1980. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska, making the inspection were:

Ray S. Decker - Geotechnical
Garold G. Ulmer - Hydraulics and Hydrology
Gordon Jamison - Hydraulics and Hydrology

Mr. John Mills, President of the Twin Lakes Home Owners Association, and Mr. C. R. Hertling, local home owner, visited the inspection team on site and were interviewed for a short period during the inspection.

b. Dam.

- (1) Geology and Soils (abutment and embankment). The embankment is situated in the loess mantled uplands on the eastern border of the Ozark Physiographic Province. The predominate soil association is the Memphis-Loring silty clay loam. The predominate structural features are the Radio Tower Structure, Jackson Fault and Cape Girardeau Fault. The embankment is located in Seismic Zone 3 (coefficient 0.10).

Samples taken on the embankment by hand auger at a depth of approximately 2 feet were field classified as CL-CH and are derived from the loess mantle. This mantle is 5 to 20 feet thick and covers a bedrock of Ordovician age. Dolomitic gravels in the alluvium suggest that the unexposed bedrock formation is the Rock Levee formation of intercolated limestones and dolomites without significant secondary porosity. Local wells developed in this formation are low in yield and specific gravity. The abutments rest on the loess mantle.

Seepage from the impoundment is controlled by the alluvium which is a gravelly and clayey silt. Catastrophic collapse due to leakage from the impoundment is not reported in this region. Solution cavitation was not found in the outcrops of the local limestones.

The embankment occurs in a seismic zone with a major probability of seismic activity. Earthquakes with Modified Mercalli intensities equal to or greater than V occurred in 1812, 1819, 1878, 1882, 1903, 1905, 1909, 1930, 1974, and 1977. These quakes are within a fifty-mile radial distance of the dam.

- (2) Upstream Slope. The upstream slope is well vegetated with fescue and native grasses which have provided very good protection against erosion. There are a number of crawfish

or salamander holes bored into the upstream slope varying from just above the water surface to approximately 2 feet above the water surface. There was no evidence of excessive erosion along the water line; no trees or shrubs on the slope; and no cracks, slumps, or abnormal deformations. The slope had been recently mowed and was very attractive in appearance. The lake level was approximately 1.8 feet below normal pool level at the time of inspection. Photos 5, 6 and 7 show views of the upstream slope.

- (3) Crest. The crest of this dam was constructed unusually wide (25 feet) in order to carry vehicular traffic. The length of the dam is traversed by a 21-foot wide asphaltic concrete street. The pavement was in excellent condition with no evidence of cracking or uneven settlement. The remaining crest width on each side of the pavement is well vegetated, uniform in appearance and free from cracks or erosion. A view of the crest is shown in Photo No. 4.
- (4) Downstream Slope. The downstream slope is also well vegetated with fescue and native grasses which had been recently mowed. There was no evidence of cracks, slides, slumps or erosion on the slope. There also was no evidence to indicate that the dam has been overtopped. Minimal rodent activity was observed as shown in Photo No. 14. There was no seepage along the toe of the dam or on the slope. A hand auger boring made approximately 10 feet above the toe showed no indications of water. A low volume (0.1 gallon per minute or less) seep was observed in the left (south) abutment trough as shown in Photo No. 11. The seep is iron stained and emerges at about the elevation of the principal spillway conduit. A screen of Poplar trees has been planted along the downstream crest-line from Station 1+00 to Station 4+00. The screen angles at Station 1+00 and follows down the slope to the approximate location of the outlet end of the principal spillway conduit. The trees are 3 to 4 inches in diameter and 20 to 30 feet in height. Several Apple trees have also been planted on the downstream slope. Photos 3 and 10 show views of the downstream slope.

c. Appurtenant Structures.

(1) Principal Spillway.

- (a) Inlet Structure. The inlet structure consisting of an 18-inch corrugated metal pipe drop inlet equipped with a trash rack appears to be in good operating condition. The area around the inlet was free of debris as was the trash rack. The inlet is shown in Photo No. 8.
- (b) Conduit. The inspection of the conduit was limited to a length of approximately six feet that was exposed at the

outlet end. The pipe appeared to be in excellent condition. Water standing in the plunge pool is believed to be surface runoff from the dam and abutment troughs. There was no flow from the conduit, and there was no evidence that would indicate seepage along the conduit. Photos 12 and 13 show views of the outlet end of the conduit and the plunge pool.

- (c) Stilling Basin. There is no constructed stilling basin. The principal spillway conduit outlets into the nature channel. Flows through the conduit have formed a plunge pool as shown in Photos 12 and 13. The pool is bottomed on bedrock and appears to be stable with no signs of recent erosion.

- (2) Emergency Spillway. The emergency spillway is in excellent condition. The approach channel upstream from the control section is well vegetated and free of obstructions. The asphaltic concrete control section is in excellent condition as is the downstream channel. Views of the downstream channel are shown in Photos 15, 16 and 17.

- (3) Low-Level Outlet. There is no low-level outlet.

- d. Reservoir Area. The perimeter of the reservoir is well vegetated with grass and trees. There was no evidence of excessive erosion around the water line. The reservoir does not have a siltation problem. The small upstream reservoir would act as a silt basin. Portions of the reservoir can be seen in Photos 2, 4, 5, 9, and 18.

- e. Downstream Channel.

- (1) Principal Spillway. The downstream channel that carries discharges from the principal spillway is tree lined and appears to be stable. The channel passes under a residential street approximately 600 feet downstream from the dam and merges with a natural drainageway from the north approximately 800 feet downstream from the dam.
- (2) Emergency Spillway. The downstream channel of the emergency spillway is unobstructed. Spillway discharges will enter the natural drainageway from the north approximately 700 feet downstream from the dam and 600 feet to the north from the principal spillway channel. Photo No. 1 shows a portion of the drainageway from the north in the extreme lower left corner. The area shown is the approximate location where emergency spillway flows will discharge.

3.2 EVALUATION

The structure appears to be in excellent condition with no serious potential of failure. The rodent activity should be curtailed, and the trees on the downstream crest and slope should be removed.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

There are no controlled outlet works for this dam. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillways.

4.2 MAINTENANCE OF DAM

Maintenance of the dam appears to be excellent. The trees on the downstream crestline and slope should be removed, and rodent activity should be controlled.

4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

4.5 EVALUATION

The overall appearance of this dam after 10 years of operation is excellent and can be attributed to an ongoing maintenance program. The trees which have been planted on the downstream crestline and slope are a detriment to the safety of the dam and should be removed. Rodent activity on the downstream slope, although not widespread, should be eliminated.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

- a. Design Data. No design data were available for this dam.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Cape Girardeau, MO.-ILL. 7-1/2 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection. Hydraulic/hydrologic computations are included as Appendix D of this report.
- c. Visual Observations.
 - (1) The principal spillway is in excellent condition and no problems should be encountered during operation.
 - (2) The emergency spillway is in excellent condition. Flow through the spillway will not endanger the integrity of the dam.
- d. Overtopping Potential. Survey data that was obtained on the small upstream dam and its spillway system was used in routing the probable maximum flood through it into the lower reservoir. It was determined that 24 percent of the probable maximum flood would be accommodated by the spillways of the upstream dam prior to overtopping of the dam. Two hydrologic routings were made through the upstream reservoir and dam - one assuming breaching of the dam and the other assuming no breaching. The results of the two routings did not indicate significant differences on the lower dam as shown in the table below:

<u>Frequency</u>	<u>*Maximum Depth Over Dam (Feet)</u>	<u>Duration Over Top (Hours)</u>
0.50 PMF: No Breach	-	-
Breach	-	-
0.75 PMF: No Breach	0.4	0.4
Breach	0.4	0.7
PMF: No Breach	0.7	0.6
Breach	0.5	0.8

*Minimum top of dam elevation - 449.2

The spillways are too small to pass the probable maximum flood without overtopping the dam. The spillways will pass 50% of the probable maximum flood and the 1% probability flood without overtopping. The overtopping which the embankment would experience

during the PMF (0.7 foot for 0.6 hour) is such that it should not cause excessive damage.

The results of the routings through the dam (assuming no breaching of the upper dam) are tabulated in regards to the following conditions:

<u>Frequency</u>	<u>Inflow Discharge c.f.s.</u>	<u>Outflow Discharge c.f.s.</u>	<u>Maximum Pool Elevation</u>	<u>*Maximum Depth Over Dam Feet</u>	<u>Duration Over Top Hours</u>
1/2 PMF	645	495	449.2	-	-
PMF	1360	1240	449.9	0.7	0.6

* Minimum top of dam elevation - 449.2 feet

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and a small size. Therefore, the 1/2 PMF to PMF is the test for the adequacy of the dam and its spillway.

The estimated damage zone is described in paragraph 1.2d in this report.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. Based on visual observation this dam appears to be in excellent condition and structurally stable with little potential of failure. There were no cracks, slides, slumps, eroded areas, or abnormal deformations. The crest shows no signs of abnormal settlement. The only seep observed was very low volume coming from the left abutment trough and does not appear to affect the stability of the dam. The growth of trees along the downstream crestline and on the downstream slope could ultimately impair the structural stability of the dam. Rodent activity should be eliminated.
- b. Design and Construction Data. Design and construction data were not available. The dam was constructed by Mr. Calvin Phillips. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam.
- d. Post-Construction Changes. The inspection team is not aware of any post-construction changes in the dam.
- e. Seismic Stability. This dam is located in Seismic Zone 3 as shown on Plate A-3. An earthquake of the magnitude predicted in this area could be hazardous to this dam. Stability analyses for this dam should include earthquake forces applicable to Seismic Zone 3.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Safety. Based on visual observation, this dam appears to be structurally stable and in excellent condition with little potential of failure. The spillways are unobstructed; appear to be in excellent condition; and will pass 50 percent of the probable maximum flood without overtopping the dam. Deficiencies observed during the inspection which could eventually be detrimental to the safety of this dam are the growth of trees and the rodent activity on the downstream slope. The low volume seep in the left (south) abutment trough does not appear to affect the stability of the dam but should be monitored on a periodic basis. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency for all dams having a high hazard potential classification.
- b. Adequacy of Information. Due to the lack of engineering data, the conclusions in this report are based upon performance history and visual observations. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Urgency. A program should be developed as soon as possible to monitor at regular intervals the deficiencies described in this report. The remedial measures recommended in paragraph 7.2b should be accomplished in the near future.
- d. Necessity for Further Investigation. The seepage and stability analyses recommended in paragraph 7.2b should be accomplished by the owner in the near future.
- e. Seismic Stability. This dam is located in Seismic Zone 3 as shown on Plate A-3. An earthquake of this magnitude could be hazardous to this dam. It is recommended that the prescribed seismic loading for Seismic Zone 3 be applied in any stability analyses performed for this dam.

7.2 REMEDIAL MEASURES

The following remedial measures and maintenance procedures are recommended. All remedial measures should be performed under the guidance of a registered professional engineer experienced in the design and construction of earth dams.


a. Alternatives.

- (1) The spillways will accommodate 50 percent of the probable maximum flood without overtopping the dam. No alternatives are required.


b. Operation and Maintenance Procedures.


- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by an engineer experienced in the design and construction of dams.
- (2) The trees growing on the downstream crestline and slope should be removed. Tree removal should be done under the guidance of an engineer experienced in the design and construction of dams.
- (3) Rodent holes on the downstream slope should be repaired. A program should be developed to eliminate rodent activity on the dam.
- (4) The crawfish holes along and above the water's edge are shallow and probably do not endanger the dam. They do, however, constitute a weakness where erosion can begin. In lieu of attempting to eliminate the crawfish population, it is recommended that monitoring of the holes and repair of eroded areas become a part of the maintenance program.
- (5) The low volume seep in the left (south) abutment trough should be monitored on a periodic basis.
- (6) The excellent maintenance program that accounts for the neat and clean appearance of this dam should be continued.
- (7) A program of periodic inspections should be initiated. Records of the inspections should be made a part of this project file.

APPENDIX A
MAPS



<p>Scale in feet</p> <p>2000 1000 0 2000 4000</p> <p>Contour Interval - 10'</p>	<p>N</p> <p>VICINITY TOPOGRAPHY</p> <p>NORTH TWIN LAKES DAM</p> <p>CAPE GIRARDEAU COUNTY, MISSOURI</p> <p>MO 31216</p> <p>PLATE A-1</p>
---	--





MISSOURI
SEISMIC ZONE MAP

PLATE A-3

APPENDIX B
PHOTOGRAPHS



NORTH TWIN LAKES DAM
CAPE GIRARDEAU COUNTY,
MISSOURI, MO. 31216

PHOTO INDEX

PLATE B-1



PHOTO NO. 2 - OVERVIEW FROM RIGHT UPSTREAM BANK



PHOTO NO. 3 - DOWNSTREAM SLOPE FROM LEFT END



PHOTO NO. 4 - CREST OF DAM FROM LEFT END



PHOTO NO. 5 - UPSTREAM SLOPE FROM LEFT END




PHOTO NO. 6 - CRAWDAD OR SALAMANDER HOLES ON UPSTREAM SLOPE



PHOTO NO. 7 - CLOSEUP
VIEW OF MUD MOUNDED AT
THE TOP OF DAUBER HOLES
NEAR WATERS EDGE



PHOTO NO. 8 - INLET TO PRINCIPAL SPILLWAY (18-INCH CMP)



PHOTO NO. 9 - LOOKING UPSTREAM FROM STATION 2 + 00

FORM 9



PHOTO NO. 10 - LOOKING ALONG DOWNSTREAM CREST AT OUTLET
OF PIPE SPILLWAY .




PHOTO NO. 11 - IRON STAINED SEEPAGE COMING OUT OF THE LEFT
ABUTMENT TROUGH AT ELEVATION OF THE OUTLET OF THE PIPE
SPILLWAY




PHOTO NO. 12 - OUTLET OF THE PRINCIPAL SPILLWAY PIPE



PHOTO NO. 13 - OUTLET OF PRINCIPAL SPILLWAY PIPE AND PLUNGE POOL



PHOTO NO. 14 - RODENT
HOLE ON DOWNSTREAM SLOPE
ABOUT FOUR TO FIVE FEET
ABOVE TOE



PHOTO NO. 15 - VIEW LOOKING ACROSS THE EMERGENCY SPILLWAY
FROM RIGHT END OF DAM (LOOKING NORTH)




PHOTO NO. 16 - VIEW LOOKING UPSTREAM THROUGH THE SPILLWAY



PHOTO NO. 17 - VIEW LOOKING DOWNSTREAM THROUGH THE SPILLWAY



PHOTO NO. 18 - VIEW LOOKING RIGHT TO LEFT (NORTH TO SOUTH)
ACROSS THE RESERVOIR



PHOTO NO. 19 - DOWNSTREAM HAZARDS JUST BELOW DAM



PHOTO NO. 20 - DOWNSTREAM HAZARDS JUST BELOW DAM



PHOTO NO. 21 - HOUSES DOWNSTREAM FROM DAM ON RIGHT SIDE



PHOTO NO. 22 - HOUSES DOWNSTREAM FROM DAM ON RIGHT SIDE



PHOTO NO. 23 - VIEW OF DOWNSTREAM HAZARDS





PHOTO NO. 24 - VIEW OF DOWNSTREAM HAZARDS


REVIEW

FORM 2

APPENDIX C
PROJECT PLATES





PLAN OF DAM
Scale: 1"= 100'



CENTERLINE PROFILE OF DAM
Scale As Shown

NORTH TWIN LAKE DAM #31210



Elevation in Feet (MSL)

C

APPENDIX D
HYDRAULIC AND HYDROLOGIC DATA

(

HYDROLOGIC COMPUTATIONS

1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs (see this section).
 - a. Twenty-four hour, one percent probabilistic rainfall for the dam location was taken from the data for the rainfall station at St. Genevieve, MO. as supplied by the St. Louis District, Corps of Engineers. The twenty-four hour probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis District policy and guidance for hydraulics and hydrology.
 - b. Drainage area = 0.11 square miles (70.1 acres).
 - c. Time of concentration of runoff = 15 minutes (computed from the Kirpich formula and verified by the formula from California Culverts Practice, California Highways and Public Works).
 - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the one percent probabilistic precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the invert of the principal spillway.
 - e. The total twenty-four hour storm duration losses for the one percent probabilistic storm were 4.12 inches. The total losses for the PMF storm were 4.27 inches. These data are based on SCS runoff curve No. 77 and No. 89 for antecedent moisture conditions SCS AMC II and MAC III respectively. The watershed is composed primarily of SCS soil group B (Mentro soils). Land cover is approximately 80% wooded and the remainder is grass and water.
 - f. Average soil loss rates = 0.15 inch per hour approximately (for PMF storm, AMC III).
2. The combined discharge rating consisted of three components: the flow through the principal spillway, the flow through the emergency spillway and the flow going over the top of the dam.

a. The principal spillway rating was developed by using the weir, orifice, and full conduit flow equations.

1) Weir flow equation ($Q = CLH^{1.5}$)
where C = weir coefficient = 3.4 (from SCS Engr. Memo 50)
L = effective weir length, ft. = 4.71
H = total head, ft.

2) Orifice equation - $Q = CA\sqrt{2gh}$
where C = orifice coefficient = 0.6
A = area of riser, sq. ft. = 1.77
h = total head, ft.


3) Full conduit flow equation


$$Q = a \sqrt{\frac{2gH}{1 + K_r + K_p L}}$$


where a = cross-sectional area of pipe, $\text{ft}^2 = 1.23$
H = total head, ft.
 K_r = coefficient for riser = 1.0
 K_p = coefficient for pipe friction loss = 0.0859
(ES-42, SCS NEH, Section 5)
L = length of pipe, ft. = 121

b. The flows over the dam and emergency spillway were determined by using the dam overtopping analyses (irregular top of dam) within the HEC-1 (Dam Safety Version) program.

3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The input, output and plotted hydrographs are attached in this section.







RUN DATE# 88/11/26.
TIME# 10.44.29.

NORTH TWIN LAKES DAM / NO. 10, NO. 31216
SAFETY ANALYSIS OF DAM OVERTOPPING USING ASSIGNED FLOOD FREQUENCIES
H & H ANALYSIS BY ROUTING PMF RATIOS THRU THE RESERVOIR

JOB SPECIFICATION									
NO	MHR	AMIN	IDAY	THR	THIN	METRC	IPLY	IPRT	NSTAN
285	0	5	0	0	0	0	0	3	0
			JOPLN	NMT	LHOPT	THACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

HTIOS=	.05	.10	.15	.20	.35	.50	.75	1.00
NPLAN=	1	2	3	4	5	6	7	8

[illegible]

SUB-AREA RUNOFF COMPUTATION

CALCULATION OF INFLOW HYDRO TO UPPER LAKE

ISTAQ	IECON	JPLT	JPRY	INAME	ISTAGE	IAUTO
000001	0	0	0	1	0	0

HYDROGRAPH DATA		RATIO		ISNOW		ISAME		LOCAL	
INHYG	YAREA	SNAP	TRSDA	TRSPC	ISNOW	ISAME	LOCAL	ISNOW	ISAME
1	0.08	0.00	0.08	1.00	0	1	0	0	0
2	0.08	0.00	0.08	1.00	0	1	0	0	0

PRECIP DATA	
SPFE	RMS
0.00	27.00
	R6
	102.00
	R12
	121.00
	R24
	130.00
	R40
	0.00
	R72
	0.00
	R96
	0.00

LOSS DATA										
LNHOPT	STKRK	DLTKR	RTIOL	EKAEN	STKKS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-80.00	0.00	0.00

CURVE NO = -80.00 WEYNESS = -1.00 EFFECT CN = 80.00

UNIT HYDROGRAPH DATA
LAG=... .17

RECESSION DATA

```

SIRIQ= 0.00  REGRESSION DATA  RTIQR= 1.00
          0.00  ORCSN= -.01

```

```

UNIT HYDROGRAPH 12 END OF PERIOD ORIGINALS, IC= 0.00 HOURS, LAG= 6. .17 VOL= 1.00 2.
52. 157. 101. 51. 27. 14.
RECESSION DATA RTION= 1.00
UNCSS= -.01
SRTQ= 0.00

```

[illegible]

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....


.....
.....

PLATE D-10

DAM DATA
 COORD EXPD DAMWID
 459.0 2.8 1.5 275.

CHST LENGTH
 75. 115. 260. 305.
 459.0 460.0 460.5 463.0
 ELEVATION

STATION: 889002, PLAN 1, RATIO 1
 LNU-OF-PERIOD HYDROGRAPH ORDINATES



STATION 000002, PLAN 1, RATIO 6
ANU-OF-PENIOD HYDROGRAPH ORDINATES

OUTFLOW

[illegible]

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

PLATE D-12

STATION000002

INFLOW(1); OUTFLOW(1) AND OBSERVED FLOW(1)

100

200

300

400

500

0.

0.

0.

0.


0.

0.


0.

•OVI•

PLATE D-14



C



PMF


[illegible]

STAGE - 3

	INFLW(I);	OUTFLOW(O)	AND OBSERVED FLOW(*)
200.	400.	600.	0.
		800.	1000.

• JACO •

PLATE D-20



SUB-AREA RUNOFF COMPUTATION

CALCULATION OF INFLO HYDRO TO NO TWIN LAKES RES-NO. 31216

ISTAU ICOMP IECON ITAPE JPLT JPRIT INAME ISTAGE IAUTO
000003 0 0 0 0 0 0 0 0

HYDRO 1 IUGS 2 TAREA .03 SWAP TRSDA TRSDC RATIO ISNOH ISAME LOCAL
0.00 0.00 0.00 1.00 0.00 1 0.00

PRECIP DATA R6 R12 R24 R48 R72 R96
SPEE 27.00 PMS 102.00 121.00 130.00 0.00 0.00 0.00

LOSS DATA STMTL CNSTL ALSX NIMP
LROPT STPKR DLYKR RTIOL EHAM STIKS RTIOK STIHL CNSTL ALSX NIMP
0 0.00 0.00 1.00 0.00 0.00 -1.00 -89.00 0.00 0.00

CURVE NO = -89.00 WETNESS = -1.00 EFFECT CN = 89.00

UNIT HYDROGRAPH DATA
IC= 0.00 LAG= .17

RECESSION DATA
STHTU= 0.00 GRCSNE= -.01 RTIOR= 1.00

UNIT HYDROGRAPH 12 END OF PERIOD ORIGINATES, IC= 12. 0.00 HOURS, LAG= 7. VOL= 1.00 1.
24: 73. 46. 23. 12. 7. 2. 1.

NO. DA	HR. MIN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	COMP Q	HR. MIN	PERIOD	RAIN	EXCS	LOSS	COMP Q
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	23
01	00	14	23	23	01	23	01	00	14	23	23	01	23
01	05	14	23	23	01	23	01	05	14	23	23	01	23
01	10	14	23	23	01	23	01	10	14	23	23	01	23
01	15	14	23	23	01	23	01	15	14	23	23	01	23
01	20	14	23	23	01	23	01	20	14	23	23	01	23
01	25	14	23	23	01	23	01	25	14	23	23	01	23
01	30	14	23	23	01	23	01	30	14	23	23	01	23
01	35	14	23	23	01	23	01	35	14	23	23	01	23
01	40	14	23	23	01	23	01	40	14	23	23	01	23
01	45	14	23	23	01	23	01	45	14	23	23	01	23
01	50	14	23	23	01	23	01	50	14	23	23	01	23
01	55	14	23	23	01	23	01	55	14	23	23	01	

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

.....
.....
.....

CFS
 CMFS
 INCHES
 MM
 AC-FT
 THOUS CU M

212.
 6.
 30.
 13.56
 349.81
 30.
 30.
 15.
 0.
 16.80
 428.75
 30.
 30.
 4421.
 123.
 16.50
 426.15
 30.
 30.

HYDROGRAPH AT STAD00003 FOR PLAN 1, RTIO 7

CFS
 CMFS
 INCHES
 MM
 AC-FT
 THOUS CU M

PEAK
 319.
 5.
 20.34
 518.62
 37.
 45.
 24-HOUR
 74.
 25.
 25.
 640.13
 46.
 56.
 72-HOUR
 25.
 25.
 25.
 640.13
 46.
 56.
 TOTAL VOLUME
 8932.
 250.
 33.60
 453.51
 61.
 75.

HYDROGRAPH AT STAD00003 FOR PLAN 1, RTIO 8

CFS
 CMFS
 INCHES
 MM
 AC-FT
 THOUS CU M

PEAK
 425.
 12.
 27.12
 688.82
 49.
 61.
 24-HOUR
 31.
 31.
 33.60
 853.51
 61.
 75.
 72-HOUR
 31.
 31.
 33.60
 853.51
 61.
 75.
 TOTAL VOLUME
 8843.
 250.
 33.60
 453.51
 61.
 75.

PMF

COMBINE HYDROGRAPHS

COMBINED INFLO HYDRO TO NO TWIN LAKES RES NO 31216

ISTAQ
 UM 2+3
 ICOMP
 2
 IECON
 0
 ITAPE
 0
 JPLI
 2
 JPRI
 0
 INAME
 1
 ISTAGE
 0
 IAUO
 0

SUM OF 2 HYDROGRAPHS AT UM 2+3 PLAN 1 RTIO 1

CFS
 CMFS
 INCHES
 MM
 AC-FT
 THOUS CU M

PEAK
 29.
 1.
 25.23
 7.
 11.
 11.
 6-HOUR
 16.
 16.
 25.23
 7.
 11.
 24-HOUR
 0.
 0.
 38.66
 11.
 11.
 72-HOUR
 0.
 0.
 38.66
 11.
 11.
 TOTAL VOLUME
 129.
 1.52
 1.52
 48.66
 11.
 11.

80000

SUM OF 2 HYDROGRAPHS AT UM 2+3 PLAN 1 RTIO 6					1/2 PMF
PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
65.3	14.1	4.1	4.1	4.1	127.3
10.	12.05	15.10	15.10	15.10	15.10
	305.00	383.43	383.43	383.43	383.43
	70.	88.	88.	88.	88.
	86.	100.	100.	100.	100.
CFS					
CMS					
INCHES					
AC-FT					
THOUS CU M					

	INFLOW(I);	OUTFLOW(O)	AND OBSERVED FLOW(*)
100.	200.	500.	500.
		400.	600.

• 1890 •

PLATE D-29





PLATE D-30



10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10
10 10 10 10 10 10 10 10 10 10

•000•

SUM OF 2 HYDROGRAPHS AT UM 2+3 PLAN 1 RTIO 8					
	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
CFS	1357.	307.	91.	31.	2672.
CMS	56.	9.	3.	3.	744.
INCHES		26.20	51.14	31.14	31.14
MM		665.37	790.98	790.98	790.98
AC-FT		182.	181.	181.	181.
THOUS CU M		188.	223.	223.	223.

PMF

This image shows a full page of dot grid paper. The grid consists of small, evenly spaced black dots forming a pattern of squares across the entire page. There are no margins, text, or other markings present.

PLATE D-37

STATION 000004, PLAN 1, RATIO 6
END-OF-PERIOD HYDROGRAPH ORDINATES $\frac{1}{2} \text{ PMF}$

OUTFLOW

[illegible]

STAGE


[illegible]


STATION000004

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(I*)

OVF

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00
11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	00										





AD-A106 644

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. NORTH TWIN LAKES DAM (MO 31216), M--ETC(U)

OCT 80 R S DECKER, G G JANISON, G ULMER

DACW43-81-C-0003

NL

UNCLASSIFIED


2 * 2

2 * 2



STATION000004

INFLOW (I); OUTFLOW (O) AND OBSERVED FLOW (F)
400. 600. 800. 1000. 1200. 1400.



0.0000





PLATE D-48






PLATE D-50

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS							
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8
				.05	.10	.15	.20	.35	.50	.75	1.00
HYDROGRAPH AT	000001	.09	1	.46	.93	1.39	1.86	3.25	4.63	6.91	9.29
		.19	1	1.32	2.63	3.95	5.26	9.21	13.15	19.73	26.31
ROUTED TO	000002	.00	1	.21	.42	.64	.85	1.49	2.12	3.19	4.25
		.19	1	.25	.39	.63	1.54	7.53	12.13	19.55	26.41
HYDROGRAPH AT	000003	.03	1	.21	.42	.64	.85	1.49	2.12	3.19	4.25
		.09	1	.20	1.20	1.80	2.40	4.20	6.00	9.00	12.00
2 COMBINED	UM 2+3	.11	1	.29	.58	.87	1.16	3.87	6.23	10.19	13.57
		.28	1	.83	1.52	2.15	3.12	10.96	18.23	28.61	38.44
ROUTED TO	000004	.11	1	.71	.81	1.31	.81	2.00	4.93	8.50	12.44
		.28	1	.28	.28	.38	.68	5.88	13.97	24.30	35.23

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 Sta. (2).....

RATIO OF PPE	MAXIMUM RESERVOIR STORAGE ELEVATION OUTFLOW	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS	TOP OF DAM
1.00	456.59	0.00	15.	9.	0.00	17.17	0.00	459.40
.95	457.71	0.00	12.	12.	0.00	16.00	0.00	459.27
.90	458.67	0.00	22.	24.	0.00	17.25	0.00	165.
.85	459.30	0.00	28.	54.	0.00	16.17	0.00	
.80	460.29	.66	28.	267.	1.75	15.03	0.00	
.75	460.73	.91	30.	432.	4.25	15.75	0.00	
1.00	460.89	1.09	31.	933.	5.17	15.75	0.00	

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 15th (4)

RATIO OF PMF	MAXIMUM RESERVOIR ELEVATION OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TUP OF DAM	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
		449.50	449.50	449.20		
		0.	0.	47.		
				525.		
.05	445.51	63.	7.	0.00	22.43	0.00
.10	446.16	67.	10.	0.00	23.42	0.00
.15	446.92	71.	12.	0.00	23.50	0.00
.20	447.74	77.	30.	0.00	16.17	0.00
.25	448.52	82.	200.	0.00	12.23	0.00
.30	449.15	87.	493.	0.00	12.23	0.00
.35	449.61	90.	858.	.52	12.23	0.00
.40	449.90	92.	1244.			
1.00						

ATE
LMED
— 8